KADUR DIVISION.

Notice dated Chikmagalur, 26th February 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 25th March 1929, 2 P.M. for constructing Silver Jubilee Building at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A M. to 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees four hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Silver Jubilee Building at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No claim for enhanced rates on any item of work will be allowed after the acceptance of the tender.

10. Percentage rates less than the lowest tender or estimated rates will not be accepted.

11. Rates should be given both in figures and words.

12. If disputes arise regarding the quality of work and rates the decision of the Chief Engineer is final and legally binding.

13. Work should be carried on according to specification recognised by the Mysore Public Works Department.

Approximate quantities for constructing Silver Jubilee Building at Chikmagalur.

Serial No.	Items of work	Per	Quantity	Rate
				In figures. In words.
				Rs. a. p.
1	Earthwork excavating foundation and filling basement including consolidation.	C.yd.	259	
2	Concrete in lime mortar	C.ft.	2,155	
3	Size stone in lime mortar foundation ...	,,	3,811	
4	Do basement	,,	2,348	
5	Burnt brick in lime mortar	,,	7,927	
6	Archwork Do	,,	250	
7	Burnt brick in cement mortar pillars, big, including plastering, etc., complete.	No.	10	
7a	Burnt brick in cement mortar pillars small including plastering, etc., complete.	,,	5	
8	Teakwood doors ⅓ panelled and 2/3 glazed including brass fittings, etc., complete 1½" thick.	S.ft.	383	
9	Teakwood doors panelled 1½" thick	,,	38	
10	Do windows with panelled shutters outside and glazed inside with iron bars brass rings, etc., complete. 1¼" thick.	,,	390	
11	Teakwood ventilators with glazed shutters and 2 cross iron bars, etc.	,,	208	
11a	(*a*) Circular ventilators with glazed shutters and 2 cross iron bars, etc.	,,	14	

Serial No.	Items of work	Per	Quantity	Rate In figures. In words.
				Rs. a. p.
12	Burnt stone slabs 5″ to 6″ thick dressed and fixed.	S.ft.	1,423	
13	Rolled steel beams including freight hoisting, etc., complete.	Cwt.	40	
14	Teakwood wrought and put up with wood oiling	C.ft.	392·2	
15	Sun shades to windows as per designs ...	No.	17	
16	Ornamental parapet with plastering, etc., complete.	R.ft.	68	
17	Roofing with First Class Mangalore tiles on teak reepers 2″ x 1″.	Sqr.	36·18	
18	Pukka terrace with 1 course of brick on edge 3″ surke concrete 3 courses of flat tiles and chunam plastering, etc., complete.	,,	9·29	
19	Constructing ornamental entablature to end room including cornice at top.	No.	2	
20	Constructing Ornamental pillars and pillasters in front vestibules.	L. S.		
21	Ornamentation to doors and windows ...	No.	15	
22	Chunam plastering ½″ thick	Sqr.	165·06	
23	White and colour washing	,,	165·06	
24	Flooring with First Class Mangalore tiles on 3″ concrete bed and cement pointed.	,,	21·97	
25	Flooring with 1¼″ thick Cuddapah slabs polished on 3″ concrete bed and cement pointed.	,,	6·53	
26	Boxing girders	R.ft.	33	
27	Cement pointing to basement	Sqr.	6·40	
28	Painting silicate paint 3 coats	,,	24·22	
29	Brick cornice 9″ thick complete	R.ft.	372	
30	Clearing site, etc.	L. S.		
31	Ornamental teakwood eave board 9″ x 1″ ...	R.ft.	25	
32	Fixing Zinc sheet at valleys 24 B W. G. ...	S.ft.	248	

Dated 26th February 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 22nd March 1929, at 3 P.M., for repairing Sri Markandeswaraswami Temple at Khandya, Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of rupees one hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for repairing Markandeswaraswami Temple at Khandya, Chikmagalur Taluk," in default of which, tenders will be rejected. Tenders to be opened on 23rd March 1929.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No claim for enhanced rates will be accepted after the acceptance of tender.

10. Tenders quoting as per cent more or less than the estimated rates or lowest tender will not be accepted.

11. Rates should be given both in words and figures.

12. In all matters of dispute regarding the rates and quality of work, the decision of the Superintending Engineer is final and legally binding.

13. All specifications should be according to those recognised by the Mysore Public Works Department.

Abstract estimate showing the approximate quantities for repairing Sri Markandeswaraswamy and Sri Janardhanaswamy Temples at Khandya.

Sl. No.	Items of work	Per	Quantity	Rate	
				In figures	In words
	I			Rs. a. p.	Rs. a. p.
1	Burnt brick in mortar	C.ft.	481		
2	Mattior nandi wood work wrought and put up	,,	134·50		
3	Roofing with corrugated galvanised iron sheets 24 B. W. G. with galvanised washers, screws, etc.	Sqr.	32·91		
4	Ridging-Plain galvanised iron sheet 24 B. W. G.-3'-0 wide fixed with galvanised bolts, washers, etc.	R.ft.	234		
5	Plastering with chunam mortar ..	Sqr.	4 00		
6	Providing stone pillars in front verandah to support cracked slab similar to the existing ones.	Each	...		
7	Fixing old doors with necessary repairs ...	,,	...		
8	Imbedding zinc sheets in roofing inside wall	Sqr.	3·50		
9	Clearing jungle	S.yds.	...		
10	Repairing Gopuram	Lump sum			
11	Dismantling old masonry (disfigured images)	Lump sum			
12	Providing a new teakwood battened door 1" thick-complete.	S.ft.	24		
13	White-washing the building 2 coats including clearing old walls.	Sqr.	35·00		
14	Repairing the existing floor with new mortar and cement.	,,	..		
15	Providing a kalasam of brass to gopuram ...	Each	...		
16	Removing the earthern mound in front and levelling.	C.yds	59		
	II. Approximate quantities for constructing a new kitchen in the compound:— (south-east corner).				
1	Clearing jungle rank vegetation roots entirely grubbed up.	S.yds.	...		
2	Earthwork excavation for foundation ...	C.yds.	25		
3	Stone jelly concrete in chunam ...	C.ft.	138		
4	Size stone in mortar	,,	849		
5	Chunam pointing	Sqr.	7·93		
6	Reserved junglewood work	C.ft.	7·42		
7	Roofing with galvanised corrugated iron sheets 24 B. W. G. fixed with galvanised bolts, screws, washers complete.	Sqr.	3·06		
8	Jungle wood doors—made of reserved jungle wood battened 1" thick.	S.ft.	36		
9	Reserved jungle wood windows battened 1" thick with $\frac{3}{4}$" dia. iron bars, etc., complete.	,,	25		
10	Flooring with stone slabs on concrete bed and cement pointed.	Sqr.	1·44		
11	Sundry works.—				
(a)	Repairing cills and lintels of old doors	Each	..		
(b)	Constructing hearth	,,	...		
(c)	Building steps	,,	...		
(d)	Providing mortar and pestle ...	,,	...		
(e)	Chocolate painting 2 coats ..	Sqr.	...		

Sl. No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	Rs. a. p.
	III. Approximate quantities for repairing the compouud wall.				
1	Dismantling the fallen bit of compound wall	R.ft.	265		
2	Removing the earth and forming it into a pial evenly.	S.yds.	147		
3	Spreading available slabs evenly, over pial ...	S.ft.	1,325		
4	Sundry repairs to the existing compound wall in the south and west.	L. S.	...		
	IV. Approximate quantities for Miscellaneous Works.				
1	Providing teakwood shutters to rear gate after removing the broken lintel slabs and replacing with new ones and resetting the fallen slabs of compound wall at the gate.	L. S.	...		
2	Providing shutter to Sri Anjaneyaswamy temple.	L. S.	...		
3	Providing shutters to Sri Narasimaswamy temple.	L. S.	...		
4	Do to Kshetrapala ...	L. S.	...		
5	Do to Sri Chendrasekaraswami temple.	L. S.	...		
6	Providing Asta Bhandanam	L. S.	...		
7	Fixing a garudagambham stone piller with platform, etc., complete.	L. S.	...		
8	Clearing site and removing jungle ...	S.yds.	...		

Notice dated 26th February 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 22nd March 1929, 2-30 P.M., for constructing Police Lines of eleven units at Ajjampur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 300 only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Lines at Ajjampur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No claim for enhanced rates on any item of work will be allowed after the acceptance of tender.

10. Tenders quoting as per cent more or less than the estimated rates or lowest tender will not be accepted.

11. Rates should be given both in figures and words.

12. If the disputes arise regarding quality of work and rates the decision of the Superintending Engineer is final and legally binding.

13. All specifications should be according to those recognised by the Mysore Public Works Department.

Approximate quantities for constructing Police Lines at Ajjampur :—

Serial No.	Details of work	Per	Single line of one unit	Additional lines of (10-units, quantity for 1 unit	Rate in figures and in words
1	Earthwork excavation and filling in basement including consolidation.	C.yds.	35	24	
2	Stone jelly concrete in mortar ...	C.ft.	328	232	
3	Stone in clay foundation and basement.	,,	660	463	
4	Burnt brick in clay ...	,,	774	451	
5	Do mortar ...	,,	174	141	
6	Burnt stone slabs 4½" thick dressed...	S.ft.	90	90	
7	Matti or Nandi wood wrought and put up.	C.ft.	27·75	18·10	
8	Roofing with I Class Mangalore tiles on teak reepers nailing, etc., complete.	Sqr.	5·72	4·17	
9	Ridge tiles set in mortar and cement pointing.	R.ft.	15 1/4	11	
10	Chunam plastering.. ..	Sqr.	22	12·38	
11	Nandi or matti wood doors with 1 1/4" thick battened shutters including painting, etc., complete.	S.ft.	88	88	
12	White washing two coats ...	Sqr.	22	12·38	
13	Nandi or matti wood windows with 1" battened shutters with iron bars painting, etc., complete.	S.ft.	9	9	
14	Nandi or matti ventilators with iron bars painting, etc., complete.	,,	4	4	
15	Nandi or matti eave board 9" x 1" ...	R.ft.	136	45	
16	Flooring with I Class Mangalore tiles on 3" concrete bed and cement pointing.	Sqr.	1·50	1·50	
17	Flooring with 1 1/2" Cuddapah slabs and cement pointing.	,,	90	·93	
18	Chacolate painting 2 coats outside and wood oiling inside.	,,	4·00	2·68	
19	Tarring 2 coats walls and wood work imbedded in walls.	L. S.	...	...	
20	Burnt brick in chunam coping with chunam plastering, etc.	R.ft.	50	34	
21	Woodoiling 2 coats ...	Sqr.	2·33	1·56	
22	Flooring with gravel and cow dung washing, etc.	C.yds.	2	2	
23	Chunam borders 6" thick ..	R.ft.	61	...	
24	U-shaped concrete drain including cement plastering ½" thick.	,,	29	29	
25	Providing chimney ...	No.	1	1	
26	Providing 1½" diameter pipe for draining water fixed with cement, etc.	,,	2	2	
27	Constructing seats in latrine with cement plastering.	Each	...	...	
28	Teakwood finials	No.	2	...	
29	Do pendents ...	,,	4	...	
30	Providing hearth	,,	1	1	
31	Providing mortar and pestle ...	,,	1	1	
32	Providing Nandi wood wall shelf with pegs, etc.	Sq.ft.	18	18	
33	Clearing site levelling ground.	S.yds.	...	..	

B. KRISHNA RAO,
Executive Engineer.